Name of Work: Construction of Shreeshakthi Bhavan at Abbigere in ward no.12 Shettyhalli, Shettyhalli Sub Division

Royalty Statement

Sl No	Description of Item	Unit	Aggregate/Size stone			Sand/Gravel		
			Qty	Constant	Quantity	Qty	Constant	Quantity
1	PCC 1:3:6	Cum	56.15	0.69	38.74	56.15	0.56	31.44
2	SSM	Cum	51.98	2.63	136.71	51.98	1.72	89.41
3	RCC	Cum	116.14	0.69	80.14	10.06	0.46	4.62
	Total				**255.59**	**Total**		**125.47**

Abstract

Sl No	Description of materials	Unit	Quantity	Rate / Cum (Rs)	Amount		
1	Aggregate	Cum	255.59	126.00	32204.03		
2	Sand/Dust	Cum	125.47	138.00	17314.47		
				Total	**49518.49**		

Assistant Engineer
Ward No.12
BBMP, Bengaluru

Assistant Executive Engineer
Shettyhalli Sub Division
BBMP, Bengaluru

Scanned by CamScanner